





REVISION REVISED PER VILLAGE CONSULTANT MEMO












REVISION REVISED PER VILLAGE CONSULTANT MEMO

LEGEND:



Dutchess Shepard LLC 333 Cedar Heights Road Rhinebeck, NY 12572

Dutchess Shepard LLC 333 Cedar Heights Road Rhinebeck, NY 12572

SITE ADDRESS 6 Mulberry Street Rhinebeck, NY

LOT SIZE:

135001-6170-568209 TAX MAP:

1.44 AC

RB-35 Zoning:



HILDENBRAND ENGINEERING, PLLC 208 CREAMERY ROAD HOPEWELL JUNCTION, NY 845.206.6994 Brian@HildenEng.com

UNDER NEW YORK STATE EDUCATION LAW ARTICLE 145 (ENGINEERING), SECTION 7209 (2), IT IS A VIOLATION OF THIS LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT © HILDENBRAND ENGINEERING, PLLC

> 6 MULBERRY STREET VILLAGE OF RHINEBECK


DUTCHESS COUNTY, NEW YORK


# IMPERVIOUS FIGURE

Seal	Scale:	As Shown
	Date:	April 1, 2023
	Drawn By:	
	Checked By:	ВЈН
	Project No.:	
	Sheet No.:	
	Dwg. No.:	


BRIAN HILDENBRAND, P.E.


C-300











NO. REVISION DATE

1 REVISED PER VILLAGE CONSULTANT MEMO 9/1/23




Dutchess Shepard LLC 333 Cedar Heights Road Rhinebeck, NY 12572

Dutchess Shepard LLC 333 Cedar Heights Road Rhinebeck, NY 12572

SITE ADDRESS 6 Mulberry Street Rhinebeck, NY
LOT SIZE: 1.44 AC

TAX MAP: 135001-6170-568209

Zoning: RB-35



HILDENBRAND ENGINEERING, PLLC 208 CREAMERY ROAD HOPEWELL JUNCTION, NY 845.206.6994 Brian@HildenEng.com

UNDER NEW YORK STATE EDUCATION LAW ARTICLE 145 (ENGINEERING), SECTION 7209 (2), IT IS A VIOLATION OF THIS LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT

© HILDENBRAND ENGINEERING, PLLC

6 MULBERRY STREET
VILLAGE OF RHINEBECK
DUTCHESS COUNTY, NEW YORK

PRELIMINARY
WATER & SEPTIC DETAILS

Scale: As Shown

Date: April 1, 2023

Drawn By:


Checked By: BJH


Project No.:


Sheet No.:

BRIAN HILDENBRAND, P.E. Dwg. No.:

D-100







TYPICAL DRAIN INLET

SCALE: N.T.S.

MYSDOT
APPROVED
GALVANIZED
STEEL (SIGN


FINISH GRADE


\_\_1/4"X8"X24" STEEL PLATE (WELDED)

SIGN POST DETAIL DETAIL

SCALE: N.T.S.


4'-0" MIN.






**ROOF LEADER DETAIL** SCALE: N.T.S.

# DRAINAGE TRENCH DETAIL SCALE: N.T.S.



LIGHT POLE BASE BEHIND CURB DETAIL SCALE: N.T.S.



REVISION REVISED PER VILLAGE CONSULTANT MEMO

9/1/23

LEGEND:


**Dutchess Shepard LLC** 333 Cedar Heights Road Rhinebeck, NY 12572

**Dutchess Shepard LLC** 333 Cedar Heights Road Rhinebeck, NY 12572

SITE ADDRESS 6 Mulberry Street Rhinebeck, NY LOT SIZE: 1.44 AC

135001-6170-568209

Zoning: RB-35



HILDENBRAND ENGINEERING, PLLC 208 CREAMERY ROAD HOPEWELL JUNCTION, NY 845.206.6994 Brian@HildenEng.com

UNDER NEW YORK STATE EDUCATION LAW ARTICLE 145 (ENGINEERING), SECTION 7209 (2), IT IS A VIOLATION OF THIS LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT

© HILDENBRAND ENGINEERING, PLLC


6 MULBERRY STREET VILLAGE OF RHINEBECK DUTCHESS COUNTY, NEW YORK


PRELIMINARY SITE DETAILS

Seal	Scale:	As Shown
	Date:	April 1, 2023
	Drawn By:	
	Checked By:	ВЈН
	Project No.:	
	Sheet No.:	
	Dwg. No.:	

BRIAN HILDENBRAND, P.E.

D-300






1. TEMPORARY CONCRETE WASHOUT TYPE ABOVE GRADE WILL BE CONSTRUCTED AS SHOWN ABOVE, WITH RECOMMENDED MINIMUM LENGTH AND MINIMUM WIDTH OF 10 FT.

2. THE WASHOUT WILL BE MINIMUM OF 50 FT FROM STORM DRAIN INLETS. 3. PLASTIC LINING WILL BE FREE OF HOLES, TEARS, OR OTHER DEFECTS


THAT COMPROMISE THE IMPERMEABILITY OF THE MATERIAL.

**CONCRETE WASHOUT DETAIL** SCALE: N.T.S.



NOTE: AFTER FOLDING FABRIC EDGE, BACKFILL TRENCH WITH ORIGINAL SOIL AND BUTTRESS THE SPLAY WITH MULCH OR LEAF LITTER.


## SILT FENCE DETAIL SCALE: N.T.S.



#### **INSTALLATION NOTES:**

- 1. AREA CHOSEN FOR STOCKPILING OPERATIONS SHALL BE DRY AND
- MAXIMUM SLOPE OF STOCKPILE SHALL BE 1:2. 3. UPON COMPLETION OF SOIL STOCKPILING, EACH PILE SHALL BE
- SURROUNDED WITH EITHER SILT FENCING OR STRAWBALES, THEN STABILIZED WITH VEGETATION OR COVERED.
- 4. SEE SPECIFICATIONS FOR INSTALLATION OF SILTFENCE.

### SOIL STOCKPILING DETAIL SCALE: N.T.S.



INSTALLATION NOTES

- 1. STONE SIZE USE 3" STONE
- 2. LENGTH AS REQUIRED, BUT NOT LESS THAN 50 FEET (EXCEPT ON A SINGLE RESIDENCE LOT WHERE A 30 FOOT MINIMUM LENGTH WOULD APPLY.)
- 3. THICKNESS NOT LESS THAN SIX (6) INCHES.
- 4. WIDTH 10 FOOT MINIMUM, BUT NOT LESS THAN THE FULL WIDTH AT POINTS WHERE INGRESS OR EGRESS OCCUR.
- 5. FILTER CLOTH WILL BE PLACED OVER THE ENTIRE AREA PRIOR TO PLACING OF STONE. FILTER CLOTH WILL NOT BE REQUIRED ON A SINGLE FAMILY
- RESIDENCE LOT 6. SURFACE WATER - ALL SURFACE WATER FLOWING OR DIVERTED TOWARD
- CONSTRUCTION ENTRANCES SHALL BE PIPED ACROSS THE ENTRANCE. IF PIPING IS IMPRACTICAL, A MOUNTABLE BERM WITH 5:1 SLOPES WILL BE PERMITTED.
- 7. MAINTENANCE THE ENTRANCE SHALL BE MAINTAINED IN A CONDITION WHICH WILL PREVENT TRACKING OR FLOWING OF SEDIMENT ONTO PUBLIC RIGHT OF WAY THIS MAY REQUIRE PERIODIC TOP DRESSING WITH ADDITIONAL STONE AS CONDITIONS DEMAND AND REPAIR AND/OR CLEANOUT OF ANY MEASURES USED TO TRAP SEDIMENT. ALL SEDIMENT SPILLED, DROPPED, WASHED OR TRACKED ONTO PUBLIC RIGHT OF WAY MUST BE REMOVED IMMEDIATELY.
- 8. WASHING WHEELS SHALL BE CLEANED TO REMOVE SEDIMENT PRIOR TO ENTRANCE ONTO PUBLIC RIGHT OF WAY. WHEN WASHING IS REQUIRED, IT SHALL BE DONE ON AN AREA STABILIZED WITH STONE AND WHICH DRAINS INTO AN APPROVED SEDIMENT TRAPPING DEVICE.
- 9. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER

# STABILIZED CONSTRUCTION ENTRANCE DETAIL **SCALE: N.T.S.**

### EROSION AND SEDIMENT CONTROL PLAN

THIS SWPPP AND ACCOMPANYING PROJECT PLANS IDENTIFY BOTH TEMPORARY AND PERMANENT EROSION AND SEDIMENT CONTROL MEASURES, WHICH HAVE BEEN DESIGNED IN ACCORDANCE WITH THE NEW YORK STATE STANDARDS AND SPECIFICATIONS FOR EROSION AND SEDIMENT CONTROL, LATEST REVISION. TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES WILL BE IMPLEMENTED DURING CONSTRUCTION TO MINIMIZE SOIL EROSION AND CONTROL SEDIMENT TRANSPORT OFF-SITE. PERMANENT EROSION AND SEDIMENT CONTROL MEASURES WILL BE IMPLEMENTED AFTER CONSTRUCTION TO CONTROL THE QUALITY AND QUANTITY OF STORMWATER RUNOFF FROM THE DEVELOPED SITE.

### EROSION AND SEDIMENT CONTROL MEASURES

TEMPORARY EROSION AND SEDIMENT CONTROL MEASURES TO BE UTILIZED DURING CONSTRUCTION GENERALLY INCLUDE THE FOLLOWING:

- 1. STABILIZED CONSTRUCTION ENTRANCE PRIOR TO CONSTRUCTION, STABILIZED CONSTRUCTION ENTRANCES SHALL BE INSTALLED TO REDUCE THE TRACKING OF SEDIMENT ONTO PUBLIC ROADWAYS. CONSTRUCTION TRAFFIC MUST ENTER AND EXIT THE SITE AT THE STABILIZED CONSTRUCTION ENTRANCE. THE ENTRANCE SHALL BE MAINTAINED IN GOOD CONDITION, WHICH WILL CONTROL TRACKING OF SEDIMENT ONTO PUBLIC RIGHTS-OF-WAY OR STREETS. WHEN NECESSARY, THE PLACEMENT OF ADDITIONAL AGGREGATE ATOP THE FILTER FABRIC SHALL BE DONE TO ASSURE THE MINIMUM THICKNESS IS MAINTAINED. ALL SEDIMENTS AND SOILS SPILLED, DROPPED, OR WASHED ONTO THE PUBLIC RIGHTS-OF-WAY MUST BE REMOVED IMMEDIATELY. PERIODIC INSPECTION AND NEEDED MAINTENANCE SHALL BE PROVIDED AFTER EACH SUBSTANTIAL RAINFALL EVENT.
- 2. DUST CONTROL WATER TRUCKS SHALL BE USED, AS NEEDED, DURING CONSTRUCTION TO REDUCE DUST GENERATED ON THE SITE. DUST CONTROL MUST BE PROVIDED BY THE GENERAL CONTRACTOR TO A DEGREE THAT IS ACCEPTABLE TO THE OWNER/OPERATOR, AND IN COMPLIANCE WITH THE APPLICABLE LOCAL AND STATE DUST CONTROL REQUIREMENTS.
- 3. TEMPORARY SOIL STOCKPILE MATERIALS, SUCH AS TOPSOIL, SHALL BE TEMPORARILY STOCKPILED (IF NECESSARY) ON THE SITE DURING THE CONSTRUCTION PROCESS. STOCKPILES SHALL BE LOCATED IN AN AREA AWAY FROM STORM DRAINAGE, WATER BODIES AND/OR COURSES, AND SHALL BE PROPERLY PROTECTED FROM EROSION BY A SURROUNDING SILT FENCE BARRIER OR HAY BALES WHEN LOCATED ON PAVED AREAS.
- 4. SILT FENCING PRIOR TO THE INITIATION OF AND DURING CONSTRUCTION ACTIVITIES, SILT FENCING SHALL BE ESTABLISHED ALONG THE PERIMETER OF ALL AREAS TO BE DISTURBED AS A RESULT OF THE CONSTRUCTION WHICH LIE UP GRADIENT OF WATER COURSES OR ADJACENT PROPERTIES. THESE BARRIERS MAY EXTEND INTO NON-IMPACT AREAS TO ENSURE ADEQUATE PROTECTION OF ADJACENT LANDS. CLEARING AND GRUBBING SHALL BE PERFORMED ONLY AS NECESSARY FOR THE INSTALLATION OF THE SEDIMENT CONTROL BARRIER. TO ENSURE EFFECTIVENESS OF THE SILT FENCING, DAILY INSPECTIONS AND INSPECTIONS IMMEDIATELY AFTER SIGNIFICANT STORM EVENTS SHALL BE PERFORMED BY SITE PERSONNEL. MAINTENANCE OF THE FENCE SHALL BE PERFORMED AS NEEDED.
- 5. TEMPORARY SEEDING WITHIN SEVEN DAYS AFTER CONSTRUCTION ACTIVITY CEASES ON ANY PARTICULAR AREA OF THE SITE, ALL DISTURBED AREAS WHERE THERE SHALL NOT BE CONSTRUCTION FOR LONGER THAN 14 DAYS SHALL BE TEMPORARILY SEEDED AND MULCHED TO MINIMIZE EROSION AND SEDIMENT LOSS.
- 6. TEMPORARY SEDIMENT BASIN A TEMPORARY SEDIMENT BASIN SHALL BE CONSTRUCTED TO INTERCEPT SEDIMENT LADEN RUNOFF, REDUCE THE AMOUNT OF SEDIMENT LEAVING THE DISTURBED AREAS, AND PROTECT DRAINAGE WAYS, PROPERTIES, AND RIGHTS-OF-WAY. PROJECTS THAT HAVE PROPOSED STORMWATER PONDS CAN BE USED AS TEMPORARY SEDIMENT BASINS DURING CONSTRUCTION. TEMPORARY SEDIMENT BASINS SHALL BE INSPECTED AT LEAST EVERY SEVEN CALENDAR DAYS. ALL DAMAGES CAUSED BY SOIL EROSION AND CONSTRUCTION EQUIPMENT SHALL BE REPAIRED UPON DISCOVERY. ACCUMULATED SEDIMENT SHALL BE REMOVED FROM THE SEDIMENT BASIN/TRAP WHEN IT REACHES 50 PERCENT OF THE DESIGN CAPACITY AND SHALL NOT EXCEED 50 PERCENT. SEDIMENT SHALL NOT BE PLACED DOWNSTREAM FROM THE EMBANKMENT, ADJACENT TO A STREAM, OR FLOODPLAIN.
- 7. DEWATERING DEWATERING, IF REQUIRED, SHALL NOT BE DISCHARGED DIRECTLY INTO WETLANDS, WATER COURSES, WATER BODIES, AND STORM SEWER SYSTEMS. PROPER METHODS AND DEVICES SHALL BE UTILIZED TO THE EXTENT PERMITTED BY LAW, SUCH AS PUMPING WATER INTO TEMPORARY SEDIMENT BASINS, PROVIDING SURGE PROTECTION AT THE INLET AND OUTLET OF PUMPS, FLOATING THE INTAKE OF THE PUMP, OR OTHER METHODS TO MINIMIZE AND RETAIN THE SUSPENDED SOLIDS.

PERMANENT EROSION AND SEDIMENT CONTROL MEASURES TO BE UTILIZED AFTER CONSTRUCTION GENERALLY INCLUDE THE FOLLOWING:

- 1. ESTABLISHMENT OF PERMANENT VEGETATION DISTURBED AREAS THAT ARE NOT COVERED BY IMPERVIOUS SURFACES SHALL BE SEEDED IN ACCORDANCE WITH THE ACCOMPANYING PLANS. THE TYPE OF SEED, MULCH, AND MAINTENANCE MEASURES SHALL BE FOLLOWED. ALL AREAS AT FINAL GRADE SHALL BE SEEDED AND MULCHED WITHIN SEVEN (7) DAYS AFTER COMPLETION OF THE MAJOR CONSTRUCTION ACTIVITY. ALL SEEDED AREAS SHALL BE PROTECTED WITH MULCH AND/OR HAY. FINAL SITE STABILIZATION IS ACHIEVED WHEN ALL SOIL-DISTURBING ACTIVITIES AT THE SITE HAS BEEN COMPLETED AND A UNIFORM, PERENNIAL VEGETATIVE COVER WITH A DENSITY OF 80 PERCENT HAS BEEN ESTABLISHED OR EQUIVALENT STABILIZATION MEASURES (SUCH AS THE USE OF MULCHES OR GEOTEXTILES) HAVE BEEN EMPLOYED ON ALL UNPAVED AREAS AND AREAS NOT COVERED BY PERMANENT STRUCTURES.
- 2. FINAL SEEDING AND PLANTING FINAL SEEDING AND PLANTING SHALL BE INSTALLED AS SHOWN ON THE ACCOMPANYING PLANS. FINAL SEEDING AND PLANTING WILL HELP MINIMIZE
- 3. ROCK OUTLET PROTECTION ROCK OUTLET PROTECTION SHALL BE INSTALLED AT THE LOCATIONS AS SHOWN ON THE ACCOMPANYING PLANS. THE INSTALLATION OF ROCK OUTLET PROTECTION WILL REDUCE THE DEPTH, VELOCITY, AND ENERGY OF WATER, SUCH THAT THE FLOW WILL NOT ERODE THE RECEIVING WATER COURSE OR WATER BODY.

SPECIFIC EROSION AND SEDIMENT CONTROL MEASURES, INSPECTION FREQUENCY, AND REMEDIATION PROCEDURES ARE PROVIDED IN THE SUBSEQUENT SECTIONS AND ON THE ACCOMPANYING PROJECT PLANS.

### POLLUTION PREVENTION CONTROLS

GOOD HOUSEKEEPING PRACTICES ARE DESIGNED TO MAINTAIN A CLEAN AND ORDERLY WORK ENVIRONMENT. GOOD HOUSEKEEPING MEASURES SHALL BE MAINTAINED THROUGHOUT THE CONSTRUCTION PROCESS BY THOSE PARTIES INVOLVED WITH THE DIRECT CARE AND DEVELOPMENT OF THE SITE. THE FOLLOWING MEASURES SHOULD BE IMPLEMENTED TO CONTROL THE POSSIBLE EXPOSURE OF HARMFUL SUBSTANCES AND MATERIALS TO STORMWATER RUNOFF:

- 1. MATERIAL RESULTING FROM THE CLEARING AND GRUBBING OPERATION SHALL BE STOCKPILED AWAY FROM STORM DRAINAGE, WATER BODIES AND/OR WATERCOURSES AND SURROUNDED WITH ADEQUATE EROSION AND SEDIMENT CONTROL MEASURES. SOIL STOCKPILE LOCATIONS SHALL BE EXPOSED NO LONGER THAN 14 DAYS BEFORE SEEDING.
- 2. EQUIPMENT MAINTENANCE AREAS SHALL BE PROTECTED FROM STORMWATER FLOWS AND SHALL BE SUPPLIED WITH APPROPRIATE WASTE RECEPTACLES FOR SPENT CHEMICALS, SOLVENTS, OILS, GREASES, GASOLINE, AND ANY POLLUTANTS THAT MIGHT CONTAMINATE THE SURROUNDING HABITAT AND/OR WATER SUPPLY. EQUIPMENT WASH-DOWN ZONES SHALL BE LOCATED WITHIN AREAS DRAINING TO SEDIMENT CONTROL DEVICES.
- 3. THE USE OF DETERGENTS FOR LARGE-SCALE (I.E., VEHICLES, BUILDINGS, PAVEMENT SURFACES, ETC.) WASHING IS PROHIBITED
- 4. MATERIAL STORAGE LOCATIONS AND FACILITIES (I.E., COVERED STORAGE AREAS, STORAGE SHEDS, ETC.) SHALL BE LOCATED ONSITE AND SHALL BE STORED ACCORDING TO THE MANUFACTURER'S STANDARDS IN A DEDICATED STAGING AREA. CHEMICALS, PAINTS, SOLVENTS, FERTILIZERS, AND OTHER TOXIC MATERIAL MUST BE STORED IN WATERPROOF CONTAINERS. RUNOFF CONTAINING SUCH MATERIALS MUST BE COLLECTED, REMOVED FROM THE SITE, TREATED AND DISPOSED AT AN APPROVED SOLID WASTE OR CHEMICAL DISPOSAL
- 5. HAZARDOUS SPILLS SHALL BE IMMEDIATELY CONTAINED TO PREVENT POLLUTANTS FROM ENTERING THE SURROUNDING HABITAT AND/OR WATER SUPPLY. SPILL KITS SHALL BE PROVIDED ONSITE AND SHALL BE DISPLAYED IN A PROMINENT LOCATION FOR EASE OF ACCESS AND USE. SPILLS GREATER THAN FIVE (5) GALLONS SHALL BE REPORTED TO THE NYSDEC RESPONSE UNIT AT 1-800-457-7362. IN ADDITION, A RECORD OF THE INCIDENT(S) AND/OR NOTIFICATIONS SHALL BE DOCUMENTED AND ATTACHED TO THE SWPPP.
- 6. PORTABLE SANITARY WASTE FACILITIES SHALL BE PROVIDED ONSITE FOR WORKERS AND SHALL BE PROPERLY MAINTAINED.
- 7. DUMPSTERS AND/OR DEBRIS CONTAINERS SHALL BE LOCATED ONSITE AND SHALL BE OF ADEQUATE SIZE TO MANAGE RESPECTIVE MATERIALS. REGULAR COLLECTION AND DISPOSAL OF
- 8. TEMPORARY CONCRETE WASHOUT FACILITIES SHOULD BE LOCATED A MINIMUM OF 50 FEET FROM STORM DRAIN INLETS, OPEN DRAINAGE FACILITIES, AND WATERCOURSES. EACH FACILITY SHOULD BE LOCATED AWAY FROM CONSTRUCTION TRAFFIC OR ACCESS AREAS TO PREVENT DISTURBANCE OR TRACKING. A SIGN SHOULD BE INSTALLED ADJACENT TO EACH WASHOUT FACILITY TO INFORM CONCRETE EQUIPMENT OPERATORS TO UTILIZE THE PROPER FACILITIES. WHEN TEMPORARY CONCRETE WASHOUT FACILITIES ARE NO LONGER REQUIRED FOR THE WORK, THE HARDENED CONCRETE SHALL BE REMOVED AND DISPOSED OF. MATERIALS USED TO CONSTRUCT THE TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE REMOVED AND DISPOSED OF. HOLES, DEPRESSIONS OR OTHER GROUND DISTURBANCE CAUSED BY THE REMOVAL OF THE TEMPORARY CONCRETE WASHOUT FACILITIES SHALL BE BACKFILLED AND/OR REPAIRED, SEEDED, AND MULCHED FOR FINAL STABILIZATION.
- 9. NON-STORMWATER COMPONENTS OF SITE DISCHARGE MUST BE CLEAN WATER. WATER USED FOR CONSTRUCTION, WHICH DISCHARGES FROM THE SITE, MUST ORIGINATE FROM A PUBLIC WATER SUPPLY OR PRIVATE WELL APPROVED BY THE HEALTH DEPARTMENT. WATER USED FOR CONSTRUCTION THAT DOES NOT ORIGINATE FROM AN APPROVED PUBLIC SUPPLY MUST NOT DISCHARGE FROM THE SITE. IT CAN BE RETAINED IN THE PONDS UNTIL IT INFILTRATES AND EVAPORATES.

GENERAL SITE EROSION CONTROL INSPECTION AND MAINTENANCE TABLE				
MAINTENANCE ITEM	FREQUENCY	DESCRIPTION OF INSPECTION PARAMETERS	DESCRIPTION OF REMEDY PROCEDURES	
SITE STRUCTURES	ANNUAL & AFTER MAJOR STORMS	-ACCUMULATED SEDIMENT IN CATCH BASIN SUMPS -ACCUMULATED DEBRIS AND LITTER -DAMAGE OR FATIGUE OF STORM STRUCTURES OR ASSOC. COMPONENTS -ACCUMULATION OF POLLUTANTS, INCLUDING OILS OR GREASE, IN CATCH BASIN SUMPS	-REMOVE -REMOVE -REPAIR AND/OR REPLACE, AS NECESSARY -REMOVE POLLUTANTS FROM CATCH BASINS. REMOVE AND/OR REPAIR POLLUTANT SOURCE	
PAVEMENT	BIANNUAL/ANNUAL	-ACCUMULATED SEDIMENT IN PAVED AREAS -ACCUMULATED DEBRIS AND LITTER	-REMOVE (SWEEP MIN 2 TIMES/YEAR) -REMOVE	
EMBANKMENTS	ANNUAL	-DIFFERENTIAL SETTLEMENT OF EMBANKMENTS -EMBANKMENT EROSION -ANIMAL BURROWS -CRACKING, BULGING, OR SLIDING OF EMBANKMENT	-STABILIZE AND RESTORE TO ORIGINAL SPECIFICATIONS -STABILIZE AND RESTORE TO ORIGINAL SPECIFICATIONS -REMOVE -STABILIZE AND RESTORE TO ORIGINAL SPECIFICATIONS	
LAWN AND LANDSCAPED AREAS	ANNUAL	-VEGETATION: 80% COVERAGE + LESS THAN 15% INVASIVE PLANT SPECIES -UNAUTHORIZED PLANTINGS -UNDESIRABLE VEGETATIVE GROWTH -ACCUMULATED DEBRIS AND LITTER	-RESTORE TO ORIGINAL SPECIFICATIONS AS PER PLANTING PLAN -REMOVE -MOW A MIN. OF 3 TIMES A YEAR. MAY INCREASE FOR AESTHETIC REASONSREMOVE	
WINTER MAINTENANCE	MONTHLY	-ACCUMULATION OF SNOW AND ICE ON CATCH BASINS, INLET AND OUTLET STRUCTURES, AND END SECTIONS -STOCK PILED SNOW NEAR INLETS AND OUTLETS -REMAINING DEICING MATERIALS	-REMOVE -REMOVE -REMOVE IN EARLY SPRING BY SWEEPING	

NO.	REVISION	DATE
1	REVISED PER VILLAGE CONSULTANT MEMO	9/1/23



Dutchess Shepard LLC 333 Cedar Heights Road Rhinebeck, NY 12572

Dutchess Shepard LLC 333 Cedar Heights Road Rhinebeck, NY 12572

SITE ADDRESS 6 Mulberry Street Rhinebeck, NY LOT SIZE: 1.44 AC

> 135001-6170-568209 TAX MAP: Zoning: RB-35



HILDENBRAND ENGINEERING, PLLC 208 CREAMERY ROAD HOPEWELL JUNCTION, NY 845.206.6994 Brian@HildenEng.com

UNDER NEW YORK STATE EDUCATION LAW ARTICLE 145 (ENGINEERING), SECTION 7209 (2), IT IS A VIOLATION OF THIS LAW FOR ANY PERSON, UNLESS ACTING UNDER THE DIRECTION OF A LICENSED PROFESSIONAL ENGINEER, TO ALTER THIS DOCUMENT

© HILDENBRAND ENGINEERING, PLLC

6 MULBERRY STREET VILLAGE OF RHINEBECK DUTCHESS COUNTY, NEW YORK

PRELIMINARY EROSION CONTROL DETAILS

Seal	Scale:	As Shown
	Date:	April 1, 2023
	Drawn By:	
	Checked By:	ВЈН

Project No.: l Sheet No. Dwg. No.:

BRIAN HILDENBRAND, P.E. LIC# 092374

D-400